





Rijkswaterstaat Ministry of Infrastructure and the Environment

Monitoring needs ageing infrastructure

COST workshop September 28 2015

Leo Klatter



Introduction



Leo Klatter

Ministry of Infrastructure and the Environment, the Netherlands

Rijkswaterstaat Major Projects and Maintenance

senior advisor Asset Management

Leo.klatter@rws.nl



Outline

- Assets Rijkswaterstaat
- Road expansion
- End of service life
- Examples monitoring
- Conclusions





Assets Rijkswaterstaat

Rijkswaterstaat manages three National Infrastructure Networks



present 1 History networks 1800



natuurlijke waterwegen bestaande waterwegen nieuw aangelegde waterwegen spoorwegen geplande spoorwegen autosnelwegen geplande autosnelwegen of verbredingen



Development networks in near future





Development infrastructure networks

- Networks for rail, road and inland water transport have matured
- No large scale new links
- Expansion within existing network
- Interlocking, connecting links as well city rings



National highways network



- 3,075 km highway, of total 60 000 km road outside cities
 - of which 2,400 km motorway,
 - and 1,259 km with traffic management systems,
 - 1 national and 5 regional traffic control centres
 - 421 dynamic route info signs
 - 90 rush-hour lanes (335 km)
- Traffic movements
 - 45 % (vehicle-kilometers)



Structures in main road network

Туре	number
Viaduct over highway	999
Viaduct in highway	1779
Movable bridges	58
Bridge - concrete small	600
Bridge - concrete large	54
Bridge - steel	31
Tunnels	22
Aqueducts	12
Total	3555





Development infrastructure networks

Issues:

- Re-use of existing "construction mass"
- Intensification use
- Higher standards for reliability and safety
- Environmental aspects; higher loads due to climate change, less impact: (low energy, low carbon => sustainable infrastructure
- Hardware: ITS, tunnels, covered roads, noise screens
- Materials: noise reducing porous asphalt, high strength concrete, FRP



Increase ICT in infrastructure networks



Rijkswaterstaat Monitoring Netherlands



Increase ICT in infrastructure networks

- Hardware: ITS, tunnels, controll centers
- Software: traffic control/ guidance:
 - now external, manual interface
 - in future in-car, automatic







Rijkswaterstaat Monitoring Netherlands



Demands Netherlands main road network

Less hindrance for users (no traffic jams):

- Construction forms and logistics -> prefab
- Work in off-peak hours
- Road lane layout during maintenance; 4- 0 systems etc
- Publicity
- Free public transport
- "Spitsmijden"; bonus for not driving during peak hours

Examples 2 large road expansion projects



Schiphol 🤸 - Amsterdam 🔛 - Almere 👜







Traffic jams in the Netherlands Amsterdam region



Commuters from Almere. Almere is only 38 years old and one of the fastest growing cities in Europe and has the ambition to become the fifth largest city (where it is currently the seventh largest city) in the Netherlands over the next twenty years. Currently, Almere is a city with over 195,000 inhabitants.



Schiphol → - Amsterdam 👜 - Almere 👜

What Rijkswaterstaat wants: better traffic flow and shorter travel time. This means expanding the capacity of the A1 - A6 - A9 - A10

- 63 km road expansion
- renovation of 5 major motorway junctions
- 130 new or adapted constructions
- renovation of 3 railway crossings
- Renovation of 100 viaducts

At the same time we take the opportunity to improve the quality of life of those living near these motorways:

- 125 km noise reducing asphalt
- 36 km noise screens
- a (land)tunnel in the A9 connecting residential areas
- Constructing the A9 partly below the surface Amstelveen
- new eco crossings



Project SAAone (yellow line) : 14 objects





Project SAAone (vellow line) :





Special solutions to reduce traffic hinder





Special solutions to reduce traffic hinder

Railway bridge over the entire A1. New embankments behind the old embankments. No mid piers. Total structure wheeled in.



Prefab bridge decks



Hollandse bridge.

7 x 50 meter spans : prefab I-beams with in situ concrete top layer.



Traffic jams in the Netherlands Rotterdam region





Heavy traffic to and from the Rotterdam harbour. Major land claiming projects on the sea (1st and 2nd Maasvlakte) in order to expand the harbour with deep sea container terminals and quays for the petrochemical industry.



Maasvlakte 🚔 - Vaanplein 💦 🛌





Maasvlakte 🚔 - Vaanplein 💦 🛌

What Rijkswaterstaat wants: better traffic flow and shorter travel time. This means expanding the capacity of the A4 – A15 – A29

- 48 km road expansion
- renovation of 2 major motorway junctions
- Ca 70 new or adapted constructions
- Renovation of ca 50 viaducts

At the same time we take the opportunity to improve the quality of life of those living near these motorways:

- noise reducing asphalt
- noise barriers



Maasvlakte 🚔 - Vaanplein 💦 🛌



The current Botlek Bridge (combined railway and motorway bridge) will be replaced by a new lifting bridge across the Oude Maas, eliminating a major shipping bottleneck in the region. The new Botlek Bridge features two bridge passages – each around 90 metres wide – and will rise some 14 metres above water level. When completed, the new Botlek Bridge, which lifts to a maximum height of 45 metres, will be one of the largest moveable bridges in the world.



Special solutions to reduce traffic hinder



During exploitation this bridge must be opened within 200 seconds, and closed within 200 seconds

Botlek bridge. Double lifting bridge with 2 main spans of 90 meters. Combined railway and motorway bridge



Prefab bridge decks

Latest developments



Prefab mid piers



Management of an ageing bridge stock





Development motorways



Number of vehicles 0.5 million (1960) -> 7 million (2007)



Age distribution bridges







End of service life



Rijkswaterstaat

|?



Prognosis cost replacement & renewal





Prognosis cost replacement & renewal (3 networks)



Replacement & Renewal Program

Technical causes:

- Condition; worn out
- Outdated technology; regulations/ maintainability
- Economics; excessive cost of maintenance (LCC)

State budget ministry Infrastructure & Environment 2015, all three networks:

- Executional program € 650 million (t/m 2020)
- Reservation € 3,9 billion (2021 t/m 2028)
- Infrastructure investment program

MIRT Projectenboek 2014





Wilhelminalaan A15





Developing monitoring

Present situation:

- Monitoring is used in case of actual risks for structural safety or durability
- Monitoring is used only when inspections or maintenance are no longer an option
- Few applications so far

Integration in Bridge Management is needed to realize full potential:

- Interaction between monitoring and inspection
- Long term operation of monitoring systems

Data management:

• Data needs interpretation to be useful for decision making



Traditional monitoring

	Duik- & Lasbedrijf Boeren B.V. 4. 073 5997041 3x 073 5997043 Vor al uw werkzaamheden underwater gespecialiseerd in brand- en laswerk, inspecties en betonstorten	DAGRAPPORT DATUM SMEL 00 OPDRACHTGEVER PLUS CONTRACT RUG D() LOKATE/SCHIP	Nr
VERKOMSCHRU	VING PROJECT NR.		
	acteriale (war)		
	outler right (war)		
	acterright (LAL)		
	acherrighe (Leel)	1) 1) 1) 1) 1) 1) 1) 1) 1) 1)	vershaven tou





Inspection based:

- Subjective results
- Labour intensive
- No continuous information flow



History of BHM in Netherlands (Rijkswaterstaat)

- Eastern Scheldt storm surge barrier; 1985-'95
- Traffic loads Moerdijk bridge; 1995
- WIM systems; 2001
- ASR affected bridges; 2000
- Brienenoord bridge, orthotrope deck; 2013
- Bridge Hagestein, main bearing system; 2014



Eastern Scheldt storm surge barrier

Evaluation design:

- Wave impacts
- Fatique steel gates
- Geotechnical aspects









Results wave impacts upper beam





Bigger, heavier, larger numbers





Weigh in motion





Example extreme axle load



20					
10		-			
oL	4	8	12	16	20



Datum:	7 december 2007
Tijd:	16:03:52
Voertuig nr:	57771400
Rijstrook:	5 R-L
Meetlocatie:	RW 004 1 HR L
Subcategorie:	0222
Snelheid (km/uur):	83

	asdruk	(ton)	
	dynamisch	statisch	lengte (m)
totaal	102,0	0,0	19,70
	dynamisch	statisch	afstand (m)
as 1	7,4		0,00
as 2	8,3		1,51
as 3	13,3		2,06
as 4	13,6		1,40
as 5	20,5		11,58
as 6	38,9		1,62



Effect on traffic loads

Transport prefab bridge elements





Results WIM measurements





ASR affected viaducts

Goal: extend service life:

- Risk of brittle collapse due to lack of shear reinforcement
- Shear strengthening is not an economical option
- Replacement of bridges is expensive and causes traffic congestion
- Large number of structures (18) with similar monitoring system
- Small ASR-expansions should be distinguished from temperature and moisture effects



5a-120 //50120 Haidiik





Automated monitoring sytem







Standard analysis reports





van Brienenoordbrug

- Fatique steel structure
- Monitoring integrated with prognostic model







Crack in steel deck of road traffic bridges

- Stress cycles cause initiation and growth of fatigue cracks
- Crack in deck; most dangerous, less visible, critical length 500 mm,





Development van Brienenoordbrug

- Monitoring system for more reliable service life prediction and inspection interval
 - 2010 2012 Lab en desktop experiment
 - 2012 2013 Bread board 4 x 2 meter steel structure
 - 2013 2014 Demonstrator van Brienenoord Brug
 - 2015 2018 Application of full prototype





Fatigue crack growth model (LEFM)





Service life prediction - number of critical cracks -





Hagestein bridge - static strength:







SLS traffic



calculation versus measurement



SLS traffic



calculation versus measurement



SLS traffic



calculation versus measurement



Cumulative excendence line main span max SLS tension stress in bottom flange



Satellite measurements: INSAR

INSAR alternative for Z plane measurements?

- INterferometric Synthetic Aperture Radar
- No physic measurement points on structure

INSAR potential:

- No traffic disturbance
- Historical data of structures where no traditional data is available
- Lower costs?





INSAR results



Findings:

1-2 mm/per year

Sudden vertical deformation around

February / March 2013

Low resolution images provide insufficient data to follow deformation in

Z plane

Analysis of high resolution images currently taking place





Conclusions: from network level

- Total system approach
- Multi level load <-> strength
 - Functional demands traffic volumes, composition, reliability, safety
 - Technical demands traffic loads
 - Local effects stress strain vibration
- Development over time

Monitoring will not function in isolation!



Conclusions: from object level

Treat object as "individuals" who form a "society"

- Applications must be customized to objects
- Goals can be different:
 - Findings one object can be applied to a group objects
 - Aimed at behavior critical element individual object
 - Result necessary to tune operational parameters, example current cathodic protection
- Attention: snapshot aspect; time for action needed; safe threshold value, extrapolation observations, integrate prognostic model



Conclusions: organizational level

- Fits in organizational processes:
 - Knowledge
 - Responsibilities
- Specific attention long term programs:
 - Able to survive reorganizations and shift of policies and priorities
- Costs:
 - All costs over lifecycle covered; including maintenance, and replacement



Discussion

